## Bluff Lake Management - Three Year Rotation

Year 1 (2017)

	Month	Management Action
木	January-July 1st	Keep nine boards/bay in Bluff Lake structure.
	July 1 <sup>st</sup>	Begin slow drawdown by removing one row of boards
	July 15 <sup>th</sup>	Remove one row of boards.
	August 1st	Remove one row of boards.
	August 15 <sup>th</sup>	Remove one row of boards.
	September 1 <sup>st</sup>	Remove one row of boards.
	Sept-November	Disk all three Bluff Lake fields (west, north, south) and shallow habitat.
	December 1 <sup>st</sup>	Add two rows of boards.
	December 15 <sup>th</sup>	Add one row of boards.
	January 1 <sup>st</sup>	Add one row of boards.
	January 15 <sup>th</sup>	Add one row of boards. Structure should be back at nine boards/bay.

\*Do not drawdown lake below six boards/bay when duck hunting GTR 1 and GTR 2.

Year 2 (2018) and Year 3 (2019)

Month	Management Action
January-July 1st	Keep nine boards/bay in Bluff Lake structure.
July 1st	Begin slow drawdown by removing one row of boards
July 15 <sup>th</sup>	Remove one row of boards.
August 1st	Remove one row of boards.
August 15th	Remove one row of boards.
September 15 <sup>th</sup>	Add one row of boards, if needed, to reach GTR 1/2 input structure.
December 1st	Add one row of boards.
December 15 <sup>th</sup>	Add one row of boards.
January 1st	Add one row of boards.
January 15 <sup>th</sup>	Add one row of boards. Structure should be back at nine boards/bay.

## Green Tree Reservoir 3 (GTR 3) Management

## When Unit is Hunted

Month	Management Action
October 1st	Add five rows of boards to Oktoc WCS and 11 rows of boards to GTR 3 WCS
November 1st	Open screw gate to 16 inches of thread. Shut when water at board height
March 1st	Remove six rows of boards from GTR 3 north WCS

## When Unit is Not Hunted

Month	Management Action
November 1st	Add three rows of boards to Oktoc WCS and eight rows of boards to GTR 3 WCS
November 15 <sup>th</sup>	Flood to board height
December 15 <sup>th</sup>	Add one row of boards to GTR 3 WCS and flood to board height
January 15 <sup>th</sup>	Add one row of boards to GTR 3 WCS and flood to board height
February 1st	Remove three rows of boards from Oktoc WCS
March 1st	Remove six rows of boards from GTR

